

NOTICE INVITING QUOTATION (NIQ)

MITL/SBIA/Electrical/NIQ for Maintenance/601

Date:19.10.2026

Subject: Installation of 11 KV RMU, providing jointing of 33KV Touchproof and Straight Joint and Jointing of 11 kV, 240 Sq. mm. Touch Proof Joint for diversion of Load From ZSS-2 to ZSS-3 At Auric Bidkin Industrial Area.

Sir,

Maharashtra Industrial Township Limited (MITL) invites sealed quotations for Installation of 11 KV RMU, providing jointing of 33KV Touchproof and Straight Through Joint and Jointing of 11 kV, 240 Sq. mm. Touch Proof Joint for diversion of Load From ZSS-2 to ZSS-3 At Auric Bidkin Industrial Area.

Sr No	Material Description	Unit	Qty	Supply	Errection	Amount
1	Providing and erecting Heat shrinkable straight through joint kit for 33 kV (E) / 33 kV (UE) XLPE HT cable 3x400 sq.mm. with necessary material as per specification no. CB-JT/HT	Each	2			
2	Supply, Jointing, Termination of 3Cx400sqmm Touch proof Joint kit (at ZSS-3)	Each	1			
3	Transportaing, Erecting, testing & commissioning 11kV, 630A, 21kA/3sec, 7 way outdoor, extensible motorised SCADA compatible RMU as per electric supply company specification consisting of 5 nos. feeder with load break switch and 2 nos. feeder with VCB as per specification no. SW-HTS / RMU SCADA (2LBS +2VCB)	Nos	1			
4	Transport, jointing, testing and comissioning of 11 KV touchproof indoor termination suitable for 11 KV, 3Cx240 Sq. mm XLPE cable.	Each	5			
5	Supply, installing, and testing of maintenance free earthing comprising of electrode of 17.2 mm diameter Low Carbon Steel with 250 micron molecular copper bonded earthing rod of Length 3m along with Carbon based environment friendly back fill ground enhancing compound required to fill up the excavated earth with required quantity (min. 125kg) complete, and recording the results specification no. EA-MF	Each	2			
6	Supplying and erecting GI strip of required size used for earthing on wall and/or any other purpose with necessary GI clamps fixed on wall painted with bituminous paint in an approved manner	Kg	100			

	with joints required as per specification no EA-EP.			
Total Excluding Taxes				
Taxes @ 18%				
Total Estimated Cost including Taxes				

Rates shall be quoted inclusive of all applicable charges (Charging permission, transportation, loading/unloading, etc.)

Total estimated cost of the work is Rs.5,42,426 Including Taxes.

The contractor has to pay 5% of security deposit in the form of DD/BG on award of work order.

The is to be executed as per general terms of contract and technical specification as guided/Directed by MITL Authorities.

Pre-qualification: The contractor shall have executed similar type of work amounting not less than Rs. 10 Lakh in last financial year. Submission of experience certificate is necessary.

Completion Period: The work shall be completed within 7 (seven) days from the date of receipt of the Work Order.

Sealed quotations are hereby invited from eligible and experienced Electrical contractors for Installation of 11 KV RMU, providing jointing of 33KV Touchproof and Straight Joint and Jointing of 11 kV, 240 Sq. mm. Touch Proof Joint at Auric Bidkin Industrial Area.

It is requested to submit your quotation on the firm letter head within seven working days i.e. before 30/10/2026 at 15:00 Hrs on following address, soft copy of the quotation shall also be submitted via email to the address mentioned below.

General Manager Electrical (Projects)
Maharashtra Industrial Township Limited (MITL)
Auric Hall Building, Shendra Industrial Area,
Chhatrapati Sambhaji Nagar, Maharashtra 431001
Contact No. +91-7506200775 Email: gmelecprojects1@auric.city



(Signature)
G.M. (Electrical Projects),
MITL